



T-Mark Plumbing, Heating, Cooling & Electric
577 Englewood Ave
Buffalo, New York 14223
(716) 864-7277

BILL TO

City of Lackawanna Library
560 Ridge Road
Lackawanna, NY 14218 USA

ESTIMATE 325503663	ESTIMATE DATE Oct 24, 2025
------------------------------	--------------------------------------

JOB ADDRESS

City of Lackawanna Library
560 Ridge Road
Lackawanna, NY 14218 USA

Project: 325495189
Technician: Brian Anderson

ESTIMATE DETAILS

Dunkirk DXL Cast Iron Boiler Installation: Installation of Dunkirk DXL Series Cast Iron Hot Water Boiler System

- Copper piping connections for boiler supply and return piping connections
- Installation of new ECM High Efficiency Circulator installed with Isolation Flanges for easy future service
- Installation of new SuperVent, all brass micro-bubble air eliminator - helps to relieve system of any remaining air in boiler.
- Installation of new properly sized expansion tank.
- Installation of new Pressure Reducing Valve with integral Backflow preventer and Pressure Relief Valve
- Installation of new 26 gauge vent pipe to tie into existing vent piping.
- Hard pipe gas line with drip leg and safe shut off valve. Leak Test all new gas piping.
- Pressure Relief Valve will be piped within 6" of the ground
- Includes Installation of Programmable or Non Programmable Honeywell T4 Thermostat

Dunkirk Cast Iron Boilers Provide The Reliability we need in Western New York

- Durable Cast Iron Heat Exchanger Provides Years of Worry Free Operation
- Up to 83.5% Thermal Efficiency
- Integrated Low Water Cut Off For Boiler Protection
- Compact, space saving design
- Lower energy consumption and gas bills

T-Mark Installation Team members to provide proper commissioning and walkthrough of boiler operations at completion.

This equipment installation qualifies for 0% financing options

Dunkirk Boiler comes with a 1 Year Full Parts Warranty & 10 Year Heat Exchanger Warranty.

T-Mark warranties the Heater, Workmanship, and all Labor for a period of 2 Years.

Note: when installing any piece of equipment tied to the domestic plumbing system - we may be required to use shut off valves in your home/building. T-Mark is not responsible for these valves, or any related work that would be required as a result of a failed shut off valve.

SERVICE	DESCRIPTION	QTY	PRICE	TOTAL
STMBLR.PSB9D	Installation of Dunkirk 82% AFUE Plymouth Cast Iron Steam Boiler - 299K BTU	2.00	\$18,947.00	\$37,894.00
NT-CHR-8.00.1000	Flush and or replace steam traps as needed.	1.00	\$4,356.81	\$4,356.81
HWH.ATM.RG240S6N	Installation of Bradford White 40 Gallon Short Natural Gas Chimney Vented Water Heater	1.00	\$2,142.00	\$2,142.00
NT-CHR-3.00.0300	Prevailing wage additional charge	1.00	\$1,605.25	\$1,605.25
E-PSB9D	Dunkirk 82% AFUE Plymouth Cast Iron Steam Boiler - 299K BTU	2.00	\$0.00	\$0.00
ECR International PSB9D				
I-E-RG240S6N	Bradford White 40 Gallon Short Natural Gas Chimney Vented Water Heater - UEF 0.58	1.00	\$0.00	\$0.00
Bradford White BRWRG240S6N				

#	DESCRIPTION	TOTAL
10-Discout	10% Discout	-\$4,599.81

SUB-TOTAL	\$41,398.25
TAX	\$0.00
TOTAL	\$41,398.25
EST. FINANCING	\$397.42

Thank you for choosing T-Mark

CUSTOMER AUTHORIZATION

THIS IS AN ESTIMATE, NOT A CONTRACT FOR SERVICES. The summary above is furnished by T-Mark Plumbing, Heating, Cooling as a good faith estimate of work to be performed at the location described above and is based on our evaluation and does not include material price increases or additional labor and materials which may be required should unforeseen problems arise after the work has started. I understand that the final cost of the work may differ from the estimate, perhaps materially. THIS IS NOT A GUARANTEE OF THE FINAL PRICE OF WORK TO BE PERFORMED. I agree and authorize the work as summarized on these estimated terms, and I agree to pay the full amount for all work performed.

Sign here

Date